

NOTICE INVITING QUOTATIONS

Quotations affixed with Rupees six revenue stamps are invited from registered contractors/ firms for **“Replacement of motor-starter cables at LIS Marval Stage 3rd”**

Quotations should reach the office of undersigned by or before **19/10/2017** upto **02:00 PM** which shall be opened on the same day or any other subsequent working day convenient to the undersigned.

The details of the works are given in ‘Annexure A’ to this notification.

90% of the payment shall be made after completion of job in full and balance 10% kept in deposit shall be released after 90 days of completion of job and to the best satisfaction of the department.

The rates to be quoted against job shall include all taxes and charges on account of carriage of materials, tools and tackles as required for execution and completion of ordered work.

Other terms and conditions shall remain the same as laid down in PWD form no. 25.

-Sd/-

No.MSD/200-01
Dated: 12.08.2017

Assistant Executive Engineer
Mechanical Irrigation Sub-division
Marval

Copy to the:

1. Executive Engineer, Mechanical Irrigation Division Srinagar for favour of information. He is requested to get the notice hosted on departmental website www.ifckashmir.com for wider publicity of this notice.
2. Junior Engineer/s, MISD Marval sub-division Srinagar for information.

OFFICE OF THE ASSISTANT EXECUTIVE ENGINEER
MECHANICAL IRRIGATION SUB-DIVISION MARVAL

Annexure A to NIQ issued under no. MSD/128-29 dated: 12.08.2017 for “Replacement of motor-starter cables at LIS Marval Stage 3rd”

S.No.	Particulars	Quantity	Rate to be quoted (Rs)
1	Shifting of old 400 sqmm Al. cable (approx. 60 ft) from LIS Marval Stage 1st to Stage 3rd. The job includes its loading, unloading and transportation charges.	01 job	_____/ - per job
2	Fitting the cable from starter to motor for unit nos. 02, 03 and 04. The job includes disconnecting and removing of fitted 240 sqmm cable, cutting of the 400sqmm cable into segments as per requirement, cutting off the damaged parts of the cable, providing, crimping and fitting of 400sqmm aluminium thimbles - 06 nos. and insulation tapping for each unit. Testing of the newly connected cables on full load.	03 jobs	_____/ - per job
3	Shifting of old 240 sqmm Al. cables from LIS Marval Stage 3rd to Divisional Stores. The job includes loading, unloading and transportation charges.	01 job	_____/ - per job

**Rates should be quoted inclusive of all taxes*

-sd/-

**Assistant Executive Engineer
Mech. Irrigation Sub-division
Marval**

**Sig of quotationer
with seal**