

NOTICE INVITING QUOTATIONS

Quotations affixed with Rupees six revenue stamps are invited from registered contractors/ firms for “**Repairs to 300HP Autotransformer starter of unit no. 01 at LIS Marval Stage 3rd**”

Quotations should reach the office of undersigned by or before **23/10/2017** upto **02:00 PM** which shall be decided on the same day or any other subsequent working day convenient to the undersigned.

The details of the works are given in ‘Annexure A’ to this notification.

90% of the payment shall be made after completion of job in full and balance 10% kept in deposit shall be released after 90 days of completion of job and to the best satisfaction of the department.

The rates to be quoted against job shall include all taxes and charges on account of carriage of materials, tools and tackles as required for execution and completion of ordered work.

Other terms and conditions shall remain the same as laid down in PWD form no. 25.

-Sd/-

No. MSD/218-19
Dated: 18.10.2017

Assistant Executive Engineer
Mechanical Irrigation Sub-division
Marval

Copy to the:

1. Executive Engineer, Mechanical Irrigation Division Srinagar for favour of information. He is requested to get the notice hosted on departmental website www.ifckashmir.com for wider publicity of this notice.
2. Junior Engineer/s, MISD Marval sub-division Srinagar for information.

OFFICE OF THE ASSISTANT EXECUTIVE ENGINEER
MECHANICAL IRRIGATION SUB-DIVISION MARVAL

Annexure A to NIQ issued under no. MSD/218-19 dated: 18.10.2017 for "**Repairs to 300HP Autotransformer starter of unit no. 01 at LIS Marval Stage 3rd**".

S.No.	Particulars	Quantity	Rate to be quoted (Rs)
1	<p>Repairs to the 300 H.P ATS of unit No. 01 at LIS Marval Stage 3rd by way of:</p> <p>Isolating and disconnecting of all incoming and outgoing leads from the starter. Stripping off the burnt, damaged wiring, busbars, etc from the starter. Complete cleaning of the starter enclosure. Providing and fitting of electro-pneumatic double timing relay with coil voltage 415V (BCH make) - 01 no., overload relay (L&T MN2 2A) - 01 no., single phase preventer - 01 no. (Minilec). Replacement of copper bus bar along with insulation between start and main contactor terminals - 03 nos. with drilling and fixing bolts, etc. Providing and connecting of suitable sized power cables with terminals to the hold-on contactor. Complete replacement of burnt control wiring with tie pins, terminal strip, etc. Dismantling and cleaning the contact points of all the contactors using carbon tetrachloride chemical. Providing and fitting of voltmeter 96x96 (0-500V) - 01 no., ammeter 96x96 (0-600A) - 01 no, tape insulated CT coils 600/5A - 06 nos. Refitting of all components of starter. Providing and crimping of 400A aluminum thimbles - 03 nos.to the starter cable entry from panel. Reconnecting of cables and testing on load.</p> <p><i>(The unserviceable scrap shall be property of the firm)</i></p>	01 c. job	_____/- per job

*Rates should be quoted inclusive of all taxes

-Sd/-

Assistant Executive Engineer
Mech. Irrigation Sub-division
Marval

Sig of quotationer
with seal